



NIQ No.: IISER-K/Civil/24-25/33

Date: 28.03.2025

## **NOTICE INVITING QUOTATION**

Assistant Executive Engineer (Civil), on behalf of Director, Indian Institute of Science Education and Research – Kolkata, Mohanpur Campus, Mohanpur -741246, invites sealed item rate (inclusive of all taxes) quotations for the under mentioned work from eligible and experienced civil contractors of CPWD/PWD/MES/KMDA/Railway/others Government Department and or other bonafide agencies dealing with Civil building works.

**Name of Work: Renovation work for painting qtr. No. D 11 at Faculty housing B block.**

- |   |                             |
|---|-----------------------------|
| (a) Estimated Cost                      | : Rs. 150,280.00            |
| (b) Earnest Money                       | : N.A.                      |
| (c) Application for Quotation           | : N.A.                      |
| (d) Receipt and open of Quotation Paper |                             |
| Up to 16.30 and 15.30 hrs of            | : 07.04.2025 and 08.04.2025 |
| (e) Time Allowed for works              | : 21 days.                  |

Quotation documents may be downloaded from the Institute website (<http://www.iiserkol.ac.in/announcements/tenders>) w. e. f. 29/03/2025 to 07/04/2025 (up to 15.30 hrs).

Quotation paper should be submitted to the **Despatch Section, Administrative cum Academic Complex, IISER Kolkata, Mohanpur – 741246** along with your comparative and justified rate (inclusive of all taxes) as per the schedule of items including all relevant documents like copies of **Trade license, PAN, GST Registration, addressed to the undersigned super scribing name of work** within 16.30 hrs of 07.04.2025 positively. For further details contact under mentioned for clarification etc. Institute will not be liable or responsible for any postal delay.

Please note that the Competent Authority reserve the right to accept or reject any or all quotations without assigning any reason whatsoever.

**Assistant Executive Engineer (Civil)**  
**IISER – Kolkata.**

Copy to:

1. DR(F & A), IISER-K.
2. Notice Board, IISER-K & File.

## Bill of quantities

**Name of work :-** Renovation work for painting in qtr no. D 11 at Faculty qtr B block.

Item No.	Sub-heads and items of work	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	sqm	50		
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	sqm	50		
3	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound ) content. (i) With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre	sqm	390.0		
4	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. (i) Two coats .	sqm	390		
5	Providing & Applying polymer modified, flexible cementitious negative side waterproofing coating with elastic waterproofing polymers on interior wall plaster surface in three coats @14.35 kg /10 sqm. one coat of self priming of cementitious waterproofing polymer(dilution with water in the ratio of 1:1) and two coats of cementitious waterproofing polymer (dilution with water in the ratio of 3:1 ) after scrapping and properly cleaning the surface to remove pre-existing paint film & loose particles till plaster is visible, complete in all respect as per the direction of Engineer-in-Charge.	sqm	60		
6	Grouting the joints of flooring tiles having joints of 3 mm width, using epoxy grout mix of 0.70 kg of organic coated filler of desired shade (0.10 kg of hardener and 0.20 kg of resin per kg), including filling / grouting and finishing complete as per direction of Engineer-in-charge.  (i) Size of Tile 600x600 mm	sqm	60		

Total Rs.=