



NIQ No.: IISER-K/Civil/24-25/23

Date: 18.12.2024

NOTICE INVITING QUOTATION

Assistant Executive Engineer (Civil), on behalf of Director, Indian Institute of Science Education and Research – Kolkata, Mohanpur Campus, Mohanpur -741246, invites sealed item rate (inclusive of all taxes) quotations for the under mentioned work from eligible and experienced civil contractors of CPWD/PWD/MES/KMDA/Railway/others Government Department and or other bonafide agencies dealing with Civil building works.

Name of Work: Construction of G. I. chainlink febric fencing for nursery adjacent to basketball court gallery near NSCB hall.

- | | |
|---|-----------------------------|
| (a) Estimated Cost | : Rs. 197,500.00 |
| (b) Earnest Money | : N.A. |
| (c) Application for Quotation | : N.A. |
| (d) Receipt and open of Quotation Paper | |
| Up to 16.30 and 15.30 hrs of | : 27.12.2024 and 30.12.2024 |
| (e) Time Allowed for works | : 30 days. |

Quotation documents may be downloaded from the Institute website (<http://www.iiserkol.ac.in/announcements/tenders>) w. e. f. 18/12/2024 to 27/12/2024 (up to 16.30 hrs).

Quotation paper should be submitted to the **Despatch Section, Administrative cum Academic Complex, IISER Kolkata, Mohanpur – 741246** along with your comparative and justified rate (inclusive of all taxes) as per the schedule of items including all relevant documents like copies of **Trade license, PAN, GST Registration, addressed to the undersigned super scribing name of work** within 16.30 hrs of 27.12.2024 positively. For further details contact under mentioned for clarification etc. Institute will not be liable or responsible for any postal delay.

Please note that the Competent Authority reserve the right to accept or reject any or all quotations without assigning any reason whatsoever.

Assistant Executive Engineer (Civil)
IISER – Kolkata.

Copy to:

1. DR(F & A), IISER-K.
2. Notice Board, IISER-K & File.

Bill of quantities

Name of work :- Construction of G. I. chainlink fabric fencing for nursery adjacent to basket ball court gallery near NSCB hall.

| Item No. | Sub-heads and items of work | Unit | Qty | Rate (Rs.) | Amount (Rs.) |
|----------|---|------|-------|------------|--------------|
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. (i) All kinds of soil | cum | 1.0 | | |
| 2 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : (i) 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources: 4 graded stone aggregate 20 mm nominal size derived from natural sources) | cum | 2.0 | | |
| 3 | Centering and shuttering including strutting, propping etc. and removal of form work for: (i) Foundations, footings, bases for columns | sqm | 12.0 | | |
| 4 | 12 mm cement plaster of mix : (i) 1:6 (1 cement: 6 fine sand) | sqm | 3.0 | | |
| 5 | Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. (i) With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre | sqm | 3.0 | | |
| 6 | Finishing walls with water proofing cement paint of required shade : (i) New work (Two or more coats applied @ 3.84 kg/10 sqm) | sqm | 3.0 | | |
| 7 | Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. | kg | 310.0 | | |
| 8 | Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. (i) Made of G.I. wire of dia 4 mm | sqm | 80.0 | | |

| Item No. | Sub-heads and items of work | Unit | Qty | Rate (Rs.) | Amount (Rs.) |
|----------|---|------|-------|------------|--------------|
| 9 | Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : (i) Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture | sqm | 90.0 | | |
| 10 | Strengthening of G.I. chainlink febric fencing with 3 mm dia G .I. wire running horizontally from pillar to pillar at top, bottom and middle of chainlink fencing as per direction of Engineer-in-charge. | rmt | 165.0 | | |

Total Rs.

Rupees