INDIAN INSTITUTE OF SCIENCE EDUCATION & RESEARCH (IISER), KOLKATA

Mohanpur Campus, Mohanpur - 741246



NIQ No.: IISER-K/Civil/25-26/35 Date: 11.12.2025

NOTICE INVITING QUOTATION

Assistant Executive Engineer (Civil), on behalf of Director, Indian Institute of Science Education and Research Kolkata, Mohanpur Campus, Mohanpur -741246, invites sealed item rate (inclusive of all taxes) quotations for the under mentioned work from eligible and experienced civil contractors of CPWD/PWD/MES/KMDA/Railway/others Government Department dealing with Civil building works.

Name of Work: Construction of cement concrete pavement and raised platform for the central store near the Medical Unit of IISER Kolkata at Mohanpur.

(a) Estimated Cost : Rs. 1,98,745.00

(b) Earnest Money : Rs. 4000.00

(c) Application for Quotation : N.A.

(d) Receipt and open of Quotation Paper

Up to 15.30 and 16.30 hrs of : 19.12.2025

(e) Time Allowed for execution of works: 12 days.

(f) EARNEST MONEY DEPOSIT

Earnest Money as mentioned above in the form of a Demand Draft of any Scheduled Bank drawn in favour of the 'Indian Institute of Science Education & Research Kolkata' payable at Kolkata having validity for 3 months or more from the last date of receipt of tenders and should be submitted with the quotation document. Quotations not accompanied by Earnest Money in the prescribed form shall be summarily rejected.

The bidder if any who had participated in the previous same quotation need not submit the EMD.

Quotation documents may be downloaded from the Institute website (http://www.iiserkol.ac.in/announcements/tenders) w. e. f. 12/12/2025 to 19/12/2025 (up to 15.30 hrs).

Quotation paper should be submitted to the **Despatch Section**, **Administrative cum Academic Complex**, **IISER Kolkata**, **Mohanpur** – **741246** along with comparative and justified rate (inclusive of all taxes) as per the schedule of items including all relevant documents like copies of **credentials** (**similar nature of work**), **Trade license**, **PAN**, **ESI & PF**, **GST Registration**, **addressed to the undersigned super scribing name of work** within **15.30** hrs of **19.12.2025** positively. For further details contact under mentioned for clarification etc. Institute will not be liable or responsible for any postal delay.

Please note that the Competent Authority reserve the right to accept or reject any or all quotations without assigning any reason whatsoever.

Assistant Executive Engineer (Civil) IISER Kolkata.

Copy to:

1. DR (F & A), IISER-K. 2. Notice Board, IISER-K 3. File.

BOQ

Name of work: - Construction of cement concrete pavement and raised platform for the central store near the Medical unit of IISER kolkata at Mohanpur.

It.	Sub-heads and items of work	Qty	Unit	Rate (Rs.)	Amount (Rs.)
No.				()	
1	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	535	kg		
	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineerin-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	34	sqm		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:		-		
	(a) 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	8.00	cum		
4	Applying priming coat:				
	With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	25	sqm		
5	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: (a) Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	25	sqm		

Total Rs