

NIQ No.: IISER-K/Civil/25-26/18

Date: 08.09.2025

## **NOTICE INVITING QUOTATION**

Assistant Executive Engineer (Civil), on behalf of Director, Indian Institute of Science Education and Research Kolkata, Mohanpur Campus, Mohanpur -741246, invites sealed item rate (inclusive of all taxes) quotations for the under mentioned work from eligible and experienced civil contractors of CPWD/PWD/MES/KMDA/Railway/others Government Department dealing with Civil building works.

**Name of Work: Renovation work for painting in qtr. no. C 02 at Faculty housing A block and qtr. no. A 10 at Staff housing of IISER Kolkata.**

(a) Estimated Cost : Rs. 1,85,460.00

(b) Earnest Money : Rs. 3,700.00

(c) Application for Quotation : N.A.

(d) Receipt and open of Quotation Paper

Up to 15.30 and 16.30 hrs of : 16.09.2025

(e) Time Allowed for execution of works : 15 days.

(f) **EARNEST MONEY DEPOSIT**

Earnest Money as mentioned above in the form of a Demand Draft of any Scheduled Bank drawn in favour of the '*Indian Institute of Science Education & Research Kolkata*' payable at **Kolkata** having validity for 3 months or more from the last date of receipt of tenders and should be **submitted** with the quotation document. Quotations not accompanied by **Earnest Money in the prescribed form shall be summarily rejected.**

Quotation documents may be downloaded from the Institute website (<http://www.iiserkol.ac.in/announcements/tenders>) w. e. f. **09/09/2025 to 16/09/2025** (up to 15.30 hrs).

Quotation paper should be submitted to the **Despatch Section, Administrative cum Academic Complex, IISER Kolkata, Mohanpur – 741246** along with comparative and justified rate (inclusive of all taxes) as per the schedule of items including all relevant documents like copies of **credentials (similar nature of work), Trade license, PAN, GST Registration, addressed to the undersigned super scribing name of work** within **15.30 hrs of 16.09.2025** positively. For further details contact under mentioned for clarification etc. Institute will not be liable or responsible for any postal delay.

Please note that the Competent Authority reserve the right to accept or reject any or all quotations without assigning any reason whatsoever.

**Assistant Executive Engineer (Civil)**  
**IISER Kolkata.**

Copy to:

1. DR (F & A), IISER-K. 2. Notice Board, IISER-K 3. File.

## Bill of quantities

**Name of work :-** Renovation work for painting in qtr no. C 02 at Faculty housing A block and qtr no. A 10 at Staff housing B block.

Item No.	Sub-heads and items of work	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	sqm	50		
2	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	sqm	16		
3	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. (i) For thickness of tiles 10 mm to 25 mm	sqm	6		
4	15 mm cement plaster on the rough side of single or half brick wall of mix : (i) 1:6 (1 cement: 6 fine sand	sqm	16		
5	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	sqm	50		
6	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound ) content. (i) With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre	sqm	50.0		
7	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. (i) Two coats .	sqm	740		
8	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. (i) Size of Tile 600x600 mm	sqm	6		

Item No.	Sub-heads and items of work	Unit	Qty	Rate (Rs.)	Amount (Rs.)
9	Filling the gap in between aluminium/ stone/ wood frame and adjacent RCC/Brick/ Stone/ wood/ Ceramic/ Gypsum work by providing weather/structural non sag elastomeric PU sealant over backer rod of approved quality as per architectural drawings and direction of Engineer-in-charge complete, complying to ASTM C920, DIN 18540- F & ISO 11600. (i) Upto 5 mm depth and 5 mm width	mtr	110		
10	Grouting the joints of flooring tiles having joints of 3 mm width, using epoxy grout mix of 0.70 kg of organic coated filler of desired shade (0.10 kg of hardener and 0.20 kg of resin per kg), including filling / grouting and finishing complete as per direction of Engineer-in-charge. (i) Size of Tile 600x600 mm	sqm	25		

Total Rs.=

Rupees