



NIQ No.: IISER-K/Civil/24-25/07

Date: 24.06.2024

NOTICE INVITING QUOTATION

Assistant Executive Engineer (Civil), on behalf of Director, Indian Institute of Science Education and Research – Kolkata, Mohanpur Campus, Mohanpur -741246, invites sealed item rate (inclusive of all taxes) quotations for the under mentioned work from eligible and experienced civil contractors of CPWD/PWD/MES/KMDA/Railway/others Government Department and or other bonafide agencies dealing with Civil building works.

Name of Work: Construction of aluminium partition and PVC flooring inside room no E 039 at A. J. C. Bose RC building.

- | | |
|---|-----------------|
| (a) Estimated Cost | : Rs. 99,140.00 |
| (b) Earnest Money | : N.A. |
| (c) Application for Quotation | : N.A. |
| (d) Receipt and open of Quotation Paper | |
| Up to 15.30 and 16.30 hrs of | : 02.07.2024 |
| (e) Time Allowed for works | : 21 days. |

Quotation documents may be downloaded from the Institute website (<http://www.iiserkol.ac.in/announcements/tenders>) w. e. f. 25/06/2024 to 02/07/2024 (up to 15.30 hrs).

Quotation paper should be submitted to the **Despatch Section, Administrative cum Academic Complex, IISER Kolkata, Mohanpur – 741246** along with your comparative and justified rate (inclusive of all taxes) as per the schedule of items including all relevant documents like copies of **Trade license, PAN, GST Registration, addressed to the undersigned super scribing name of work** within **15.30 hrs of 02.07.2024** positively. For further details contact under mentioned for clarification etc. Institute will not be liable or responsible for any postal delay.

Please note that the Competent Authority reserve the right to accept or reject any or all quotations without assigning any reason whatsoever.

Assistant Executive Engineer (Civil)
IISER – Kolkata.

Copy to:

1. DR(F & A) Officiating, IISER-K.
2. Notice Board, IISER-K & File.

Bill of quantities

Name of work :- Construction of aluminium partition and PVC floor inside room no E 039 at A. J. C. Bose RC building.

Item No.	Sub-heads and items of work	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1	Providing and fixing anodized glazed aluminium work for partition made up with 1.5 mm thick aluminium tubular section 2.5" x 1.5" as frame, fixed with rawl plugs and screws etc. including cleat angle, aluminium snap beading for glazing/ panelling, with fixing clip or with expansion hold fastners including necessary filling up of gap at junctions at top, bottom and sides with required PVC/ neoprene felt, rubber gasket along with aluminium beading, taper clip of required section etc., panel to be covered with 4 mm thick ACP (Aluminium composite panel) board including rubber gasket and taper clip etc. all complete as per direction of Engineer-in-charge.	sqm	11.0		
2	Providing and fixing anodized aluminium work for door shutter, frame made up with 1.5 mm thick aluminium tubular section 1 3/4"x1 3/4" as vertical member, top and middle section - 2"x1 3/4", bottom section 4"x 1 3/4" and with fixing clip or with expansion hold fastners including necessary filling up of gap at junctions at top, bottom and sides with required PVC/ neoprene felt, rubber gasket along with aluminium beading, taper clip of required section etc., 4 mm thick ACP (Aluminium composite panel) board and 5.5 mm thick plane float glass including rubber and taper clip and ISI marked SS hinge, rolling wheel, G channel, 6" aluminium handle, locking arrangement with conceal lock etc. all complete as per direction of Engineer-in-charge. i) Door shutter (sliding/hinged).	sqm	2.0		
3	Dismantling old PVC flooring and cleaning the surface for new PVC flooring including disposal of rubbish to the dumping ground within 50 metres lead.	sqm	30.0		
4	Supplying & laying of approved make and brand of scratch proof, flexible & homogeneous P.V.C. Vinyle flooring in required finish, fixed with synthetic acrylic adhesive after preparing the floor, levelling & smothaning when necessary with suitable putty, as per the design & instruction of the Engineer-in-charge.				
	(i) 36 inch x 6inch plank shape tiles	sqm	30.0		

Item No.	Sub-heads and items of work	Unit	Qty	Rate (Rs.)	Amount (Rs.)
5	Supplying and affixing optically clear polyester frosted film over window glass/ glass panel etc. having free from any optical defect. The film should be pasted after preparatory works without any cracking, delamination, bubbling, discolouring etc. including scaffolding & relevant others to complete in all respect as per manufacturer's specification & direction of Engineer -in-Charge.	sqm	6.0		
6	Supplying and affixing optically clear polyester sun control window film having acrylic pressure sensitive adhesive on one side & an acrylic abrasion resistant coating on the other, with composition of infrared absorbing carbon & free from any optical defect. The film characteristics should conform to ASTM E308, ASTM E903, ASTM E84 and ASHIRAE. The film should be pasted after preparatory works without any cracking, delamination, bubbling, discolouring and variation in total transmission of light across the width at any portion along the length doesn't exceed 2% over the average including scaffolding & relevant others to complete in all respect as per manufacturer's specification & direction of Engineer -in-Charge.				
	(a) Normal Quality : Film Thickness - 1.0 Mil, Glare Reduction > 45%, U factor < 1.15	sqm	3.0		

Total Rs.=

In word Rupees