



NIQ No.: IISER-K/Civil/24-25/22

Date: 17.12.2024

## **NOTICE INVITING QUOTATION**

Assistant Executive Engineer (Civil), on behalf of Director, Indian Institute of Science Education and Research – Kolkata, Mohanpur Campus, Mohanpur -741246, invites sealed item rate (inclusive of all taxes) quotations for the under mentioned work from eligible and experienced civil contractors of CPWD/PWD/MES/KMDA/Railway/others Government Department and or other bonafide agencies dealing with Civil building works.

**Name of Work: Renovation work for water closets in NSCB and ICV hall.**

- |   |                  |
|---|------------------|
| (a) Estimated Cost                      | : Rs. 113,510.00 |
| (b) Earnest Money                       | : N.A.           |
| (c) Application for Quotation           | : N.A.           |
| (d) Receipt and open of Quotation Paper |                  |
| Up to 15.30 and 16.30 hrs of            | : 26.12.2024     |
| (e) Time Allowed for works              | : 30 days.       |

Quotation documents may be downloaded from the Institute website (<http://www.iiserkol.ac.in/announcements/tenders>) w. e. f. 17/12/2024 to 26/12/2024 (up to 15.30 hrs).

Quotation paper should be submitted to the **Despatch Section, Administrative cum Academic Complex, IISER Kolkata, Mohanpur – 741246** along with your comparative and justified rate (inclusive of all taxes) as per the schedule of items including all relevant documents like copies of **Trade license, PAN, GST Registration, addressed to the undersigned super scribing name of work** within 15.30 hrs of 26.12.2024 positively. For further details contact under mentioned for clarification etc. Institute will not be liable or responsible for any postal delay.

Please note that the Competent Authority reserve the right to accept or reject any or all quotations without assigning any reason whatsoever.

**Assistant Executive Engineer (Civil)**  
**IISER – Kolkata.**

Copy to:

1. DR(F & A), IISER-K.
2. Notice Board, IISER-K & File.

## **Bill of quantities**

**Name of work :-** Renovation work for water closets at NSCB and ICV hall.

Item No.	Sub-heads and items of work	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1	Dismantling of flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	each	12		
2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. (i) For thickness of tiles above 25 mm and up to 40 mm.	sqm	25		
3	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. (i) Nominal concrete 1:3:6 or richer mix (including equivalent design mix)	cum	2.0		
4	Providing and fixing white vitreous china water closet squatting pan (Indian type) : (i) Orissa pattern W.C. pan of size 580x440 mm	each	12		
5	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete. (i) 10 litre capacity - White	each	12		
6	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement: 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sq.m including pointing the joints with white cement and matching pigments etc., complete.	sqm	25		

Item No.	Sub-heads and items of work	Unit	Qty	Rate (Rs.)	Amount (Rs.)
6	Providing & Applying polymer modified, flexible cementitious negative side waterproofing coating with elastic waterproofing polymers on interior wall plaster surface in three coats @14.35 kg /10 sqm. one coat of self priming of cementitious waterproofing polymer(dilution with water in the ratio of 1:1) and two coats of cementitious waterproofing polymer (dilution with water in the ratio of 3:1 ) after scrapping and properly cleaning the surface to remove pre-existing paint film & loose particles till plaster is visible, complete in all respect as per the direction of Engineer-in-Charge.	sqm	20		

Total Rs. =

Rupees