

NIQ No.: IISER-K/Civil/25-26/17

Date: 21.08.2025

NOTICE INVITING QUOTATION

Assistant Executive Engineer (Civil), on behalf of Director, Indian Institute of Science Education and Research – Kolkata, Mohanpur Campus, Mohanpur -741246, invites sealed item rate (inclusive of all taxes) quotations for the under mentioned work from eligible and experienced civil contractors of CPWD/PWD/MES/KMDA/Railway/others Government Department and or other bonafide agencies dealing with Civil building works.

Name of Work: Repainting of galleries at basket ball and volley ball ground of IISER Kolkata at Mohanpur.

- | | |
|---|-----------------------------|
| (a) Estimated Cost | : Rs. 193,930.00 |
| (b) Earnest Money | : N.A. |
| (c) Application for Quotation | : N.A. |
| (d) Receipt and open of Quotation Paper | |
| Up to 15.30 and 16.30 hrs of | : 22.08.2025 and 29.08.2025 |
| (e) Time Allowed for works | : 21 days. |

Quotation documents may be downloaded from the Institute website (<http://www.iiserkol.ac.in/announcements/tenders>) w. e. f. 22/08/2025 to 29/08/2025 (up to 15.30 hrs).

Quotation paper should be submitted to the **Despatch Section, Administrative cum Academic Complex, IISER Kolkata, Mohanpur – 741246** along with your comparative and justified rate (inclusive of all taxes) as per the schedule of items including all relevant documents like copies of **Trade license, PAN, GST Registration, addressed to the undersigned super scribing name of work** within 15.30 hrs of 29.08.2025 positively. For further details contact under mentioned for clarification etc. Institute will not be liable or responsible for any postal delay.

Please note that the Competent Authority reserve the right to accept or reject any or all quotations without assigning any reason whatsoever.

Assistant Executive Engineer (Civil)
IISER – Kolkata.

Copy to:

1. DR(F & A), IISER-K.
2. Notice Board, IISER-K & File.

Bill of quantities

Name of work :- Repainting of galleries at basket ball and volly ball ground of IISER Kolkata at Mohanpur.

It. No.	Sub-heads and items of work	Qty	Unit	Rate (Rs.)	Amount (Rs.)
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	730	sqm		
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	50	sqm		
3	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. (a) With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre	730	sqm		
4	Finishing walls with Acrylic Smooth exterior paint of required shade: a) Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	730	sqm		

Total Rs.