

NIQ No.: IISER-K/Civil/25-26/23

Date:07.10.2025

NOTICE INVITING QUOTATION

Assistant Executive Engineer (Civil), on behalf of Director, Indian Institute of Science Education and Research Kolkata, Mohanpur Campus, Mohanpur -741246, invites sealed item rate (inclusive of all taxes) quotations for the under mentioned work from eligible and experienced civil contractors of CPWD/PWD/MES/KMDA/Railway/others Government Department dealing with Civil building works.

Name of Work: Construction of partition work in the room no 214 of CV Raman AAC building of IISER Kolkata.

- | | |
|---|-------------------|
| (a) Estimated Cost | : Rs. 1,99,500.00 |
| (b) Earnest Money | : Rs. 4,000.00 |
| (c) Application for Quotation | : N.A. |
| (d) Receipt and open of Quotation Paper | |
| Up to 15.30 and 16.30 hrs of | : 17.10.2025 |
| (e) Time Allowed for execution of works | : 15 days. |
| (f) <u>EARNEST MONEY DEPOSIT</u> | |

Earnest Money as mentioned above in the form of a Demand Draft of any Scheduled Bank drawn in favour of the '*Indian Institute of Science Education & Research Kolkata*' payable at **Kolkata** having validity for 3 months or more from the last date of receipt of tenders and should be **submitted** with the quotation document. Quotations not accompanied by **Earnest Money in the prescribed form shall be summarily rejected.**

Quotation documents may be downloaded from the Institute website (<http://www.iiserkol.ac.in/announcements/tenders>) w. e. f. **07/10/2025 to 14/10/2025** (up to 15.30 hrs).

Quotation paper should be submitted to the **Despatch Section, Administrative cum Academic Complex, IISER Kolkata, Mohanpur – 741246** along with comparative and justified rate (inclusive of all taxes) as per the schedule of items including all relevant documents like copies of **credentials (similar nature of work), Trade license, PAN, GST Registration, addressed to the undersigned super scribing name of work** within **15.30 hrs of 17.10.2025** positively. For further details contact under mentioned for clarification etc. Institute will not be liable or responsible for any postal delay.

Please note that the Competent Authority reserve the right to accept or reject any or all quotations without assigning any reason whatsoever.

Assistant Executive Engineer (Civil)
IISER Kolkata.

Copy to:

1. DR (F & A), IISER-K. 2. Notice Board, IISER-K 3. File.

Schedule of Items

Name of work : Construction of partition work in the room no 214 of CV Raman AAC building of IISER Kolkata.

It. No.	Description of Items	Unit	Quantity	Rate	Amount (Rs.)
1	Providing and fixing partition upto ceiling height consisting of G.I. frame and required board, including providing and fixing of frame work made of special section power pressed/ roll form G.I. sheet with zinc coating of 120 gms/sqm(both side inclusive), consisting of floor and ceiling channel 50 mm wide having equal flanges of 32 mm and 0.50 mm thick, fixed to the floor and ceiling at the spacing of 610 mm centre to centre with dash fastener of 12.5 mm dia meter 50 mm length or suitable anchor fastener or metal screws with nylon plugs and the studs 48 mm wide having one flange of 34 mm and other flange 36 mm and 0.50 mm thick fixed vertically within flanges of floor and ceiling channel and placed at a spacing of 610 mm centre to centre by 6 mm dia bolts and nuts, including fixing of studs along both ends of partition fixed flush to wall with suitable anchor fastener or metal screws with nylon plugs at spacing of 450 mm centre to centre, and fixing of boards to both side of frame work by 25 mm long dry wall screws on studs, floor and ceiling channels at the spacing of 300 mm centre to centre. The boards are to be fixed to the frame work with joints staggered to avoid through cracks, M.S. fixing channel of 99 mm width (0.9 mm thick having two flanges of 9.5 mm each) to be provided at the horizontal joints of two boards, fixed to the studs using metal to metal flat head screws, including jointing and finishing to a flush finish with recommended jointing compound, jointing tape, angle beads at corners (25 mm x 25 mm x 0.5 mm), joint finisher and two coats of primer suitable for board as per manufacture's specification and direction of engineer in charge all complete. 1. 66 mm overall thickness Partition with 8 mm thick double skin Calcium Silicate Board made with Calcareous & Siliceous materials reinforced with cellulose fiber manufactured through autoclaving process with Compressive Strength 225 kg/sq.cm, Bending Strength 100 kg./sq.cm	sqm	50.00		
2	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fastlugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately): Kiln seasoned and chemically treated bollock wood	cum	0.03		
3	Providing and fixing 12 mm thick frameless toughened glass door shutter of approved brand and manufacture, including providing and fixing top & bottom pivot & double action hydraulic floor spring type fixing arrangement and making necessary holes etc. for fixing required door fittings, all complete as per direction of Engineer-in-charge (Door handle, lock and stopper etc. to be paid separately).	sqm	6.00		
4	Providing and fixing Brass 100mm mortice latch and lock with 6 levers without pair of handles (best make of approved quality) for Glass doors including necessary cutting and making good etc. complete.	nos.	3.00		

5	Providing and fixing S. S. (Grade 304) tubular handle bar 32 mm outer dia & 1000 mm long with SS screws etc .complete as per direction of Engineer-in-Charge.	nos.	3.00		
6	Distempering with 1st quality acrylic Distemper(ready mixed), having VOC (Volatile OrganicCompound) content less than 50 grams/ litre, of approved brand and manufacture, including applying of water thinable cement primer and additional coats wherever required, to achieve even shade and colour.	sqm	100.00		
7	Providing and fixing of frosted films of approved quality on the glass pannels at required position as per direction of Engineer-in-Charge.	sqm	6.00		