



NIQ No.: IISER-K/Civil/26-27/06

Date: 29.06.2026

## **NOTICE INVITING QUOTATION**

Assistant Executive Engineer (Civil), on behalf of Director, Indian Institute of Science Education and Research Kolkata, Mohanpur Campus, Mohanpur -741246, invites sealed item rate (inclusive of all taxes) quotations for the under mentioned work from eligible and experienced civil contractors of CPWD/PWD/MES/KMDA/Railway/others Government Department dealing with Civil building works.

**Name of Work: Renovation work in qtr no. C 22 at Faculty Housing C block of IISER Kolkata.**

- |   |                  |
|---|------------------|
| (a) Estimated Cost                      | : Rs.2,06,900.00 |
| (b) Earnest Money                       | : Rs.4500.00     |
| (c) Application for Quotation           | : N.A.           |
| (d) Receipt and open of Quotation Paper |                  |
| Up to 15.30 and 16.30 hrs of            | : 07.07.2026     |
| (e) Time Allowed for execution of works | : 15 days.       |
| (f) <b><u>EARNEST MONEY DEPOSIT</u></b> |                  |

Earnest Money as mentioned above in the form of a Demand Draft of any Scheduled Bank drawn in favour of the '*Indian Institute of Science Education & Research Kolkata*' payable at **Kolkata** having validity for 3 months or more from the last date of receipt of tenders and should be **submitted** with the quotation document. Quotations not accompanied by **Earnest Money in the prescribed form shall be summarily rejected.**

Quotation documents may be downloaded from the Institute website (<http://www.iiserkol.ac.in/announcements/tenders>) w. e. f. 29/06/2026 to 07/07/2026 (up to 15.30 hrs).

Quotation paper should be submitted to the **Dispatch Section, Administrative cum Academic Complex, IISER Kolkata, Mohanpur – 741246** along with comparative and justified rate (inclusive of all taxes) as per the schedule of items including all relevant documents like copies of **credentials (similar nature of work), Trade license, PAN, ESI & PF, GST Registration, addressed to the undersigned super scribing name of work** within 15.30 hrs of 07.07.2026 positively. For further details contact under mentioned for clarification etc. Institute will not be liable or responsible for any postal delay.

Please note that the Competent Authority reserve the right to accept or reject any or all quotations without assigning any reason whatsoever.

**Assistant Executive Engineer (Civil)**  
**IISER Kolkata.**

Copy to:

1. DR (F & A), IISER-K. 2. Notice Board, IISER-K 3. File.

## BOQ

**Name of work :-** Renovation work in qtr no. C 22 at Faculty housing C block of IISER Kolkata.

Item No.	Sub-heads and items of work	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	sqm	20		
2	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	sqm	20		
3	15 mm cement plaster on the rough side of single or half brick wall of mix : (i) 1:6 (1 cement: 6 fine sand	sqm	20		
4	Providing & Applying polymer modified, flexible cementitious negative side waterproofing coating with elastic waterproofing polymers on interior wall plaster surface in three coats @14.35 kg /10 sqm. one coat of self priming of cementitious waterproofing polymer(dilution with water in the ratio of 1:1) and two coats of cementitious waterproofing polymer (dilution with water in the ratio of 3:1 ) after scrapping and properly cleaning the surface to remove pre-existing paint film & loose particles till plaster is visible, complete in all respect as per the direction of Engineer-in-Charge.	sqm	80		
5	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound ) content. (i) With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre	sqm	330		

Item No.	Sub-heads and items of work	Unit	Qty	Rate (Rs.)	Amount (Rs.)
6	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.				
	(i) Two coats .	sqm	330		
7	Grouting the joints of flooring tiles having joints of 3 mm width, using epoxy grout mix of 0.70 kg of organic coated filler of desired shade (0.10 kg of hardener and 0.20 kg of resin per kg), including filling / grouting and finishing complete as per direction of Engineer-in-charge.				
	(i) Size of Tile 600x600 mm	sqm	40		
8	Removing old putty by scrapping, rubbing sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	sqm	80		
9	Providing and applying white cement based water proof putty, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	sqm	80		
10	Applying two coats of solvent free, water based, epoxy protective coating for indoor damp surfaces having water proofing properties by mixing in proportion (Part A : Part B = 2 : 1 (by weight)) or as per manufacturer's specification for making water proofing layer on vertical indoor wall surface. One pack of 600 grams covers approx 20 sqft in 2 coats. The operation shall be carried out after scrapping and properly cleaning the surface to remove loose particles, complete in all respect as per the direction of Engineer- in-Charge.	sqm	80		